

TARIME TOWN COUNCIL					
SCHEDULES OF GENERAL MATERIALS FOR THE PROPOSED COMPLETION OF TARIME TOWN COUNCIL					
ADMINISTRATION BLOCK 2022					
ITEM	DESCRIPTION	QTY	UNIT	PRICE-TZS	AMOUNT
A.	CEILING FOR THE INTERNAL AND FOR THE EAVES				
1	9mm thick 600x600mm suspended vinly ceiling tiles	3895	PC'S		
2	100mmx100mm Moulded Cornice (8ft)	192	PC'S		
3	Aluminium rail for holding vinly tiles	20	Box		
4	Aluminium rail hangers including other accessories	20	Box		
5	Screw 1.25" 800pcs/box	1	Box		
6	Treated softwood Timber 2" X 2" (3.6m)	365	Pcs		
7	Nails 4"	100	Kg		
8	Nails 3"	100	Kg		
9	Concrete nails 3" and 4"	50	Box		
	SUB-TOTAL FOR CEILING				
B.	DOOR				
	45mm thick hardwood Mninga door shutter				
1	(D2) 1800 x 2400 mm high double door	5	PC'S		
2	(D3) 900 x 2400 mm high door	66	PC'S		
3	(D4) 800 x 2400 mm high door	27	PC'S		
4	(D5) 1000 x 2400 mm high door	4	PC'S		
5	Frames Glass 6mm thick clear glass				
6	(D2) 1800 x 400 mm high double door	5	PC'S		
7	(D3) 900 x 400 mm high door	66	PC'S		
8	(D4) 800 x 400 mm high door	27	PC'S		
9	(D5) 1000 x 400 mm high door	4	PC'S		
	IronMongeries				
10	Mortice lock Three lever - ref: union model Na 1223 case 65; RebTED COMPONENT MODEL 2979	71	No		
11	Mortice lock Two lever - ref: union model Na 1223 case 65; Rebled component Model 2979	24	No		
12	100mm long DSSW Brass butt hinges type U509/2	150.0	Pairs		
13	30mm diameter rubber door stop fixed to concrete floor or blockwork base	104	No		
14	Hydraulic door check surface/fixing to surface, UNION model8573	95	No		
15	100mm long Brass flush bolts	10	No		
16	Gypsum screw 1000Pcs/Box	1.0	Box		
	Metal Works				
	Strong Room Doors and frames	2	No		
	Balustrades:				

17	900mm high composite unit stainless steel balustrades; consting of 75mm diameter handrails; 30mm diameter vertical main balustraders; 25mm diameter infill balusters spaced at 200mm centres; 30mm diameter horizontal rails;all welded together; including balls; rings and all other accessories: (Court Yard/Void)	129	m		
18	1200mm high steel black pipe balustrades; constituting of 75mm diameter handrails; 30mm diameter vertical main balustraders; 25mm diameter infill balusters spaced at 200mm centres; 30mm diameter horizontal rails; all welded together; including balls; rings and all other anchoring accessories; red oxide primed (External Balcony)	220	m		
STAIR CASE TYPE I:					
19	900mm high composite unit stainless steel balustrades;consting of 75mm diameter handrails; 30mm diameter vertical main balustraders; 25mm diameter infill balusters spaced at 200mm centres; 30mm diameter horizontal rails; all welded together; including balls; rings and all other accessories.	25	M		
STAIR CASE TYPE II:					
20	STAIR CASE TYPE II:900mm high composite unit stainless steel balustrades;consting of 75mm diameter handrails; 30mm diameter vertical main balustraders; 25mm diameter infill balusters spaced at 200mm centres; 30mm diameter horizontal rails; all welded together; including balls; rings and all other accessories.	25	M		
SUB-TOTAL FOR DOORS					
C. FINISHING					
Floor finishing - (ratio 1:6)					
1	Sand	10	Trips		
2	Cement-50kgs	100	Bags		
3	400 x 400 x 8mm Thick Non slippery floor tiles (1.92 Sgm/Box)	20	Box		
4	Skirting (600 mm long; 25No/Box)	40	Box		
5	Spacer	20	Packet		
6	Aluminium strip to edges of Tiles (3m long)	40	Pcs		
7	STUCCO glue 20L/Bucket	60	Bucket		
8	6X 25mm brass weather bars	15	m		
finishing cont'ed					
WORKTOP/RECEPTION/ PARTITION					
9	Aluminium Partition	15	M2		
10	Marble worktop size 2000 x600mm	10	Pcs		
11	6mm thick clear glass	5	M2		
12	25mm thick hardwood well finished	8	M2		
Wall Finishing					
	Sand 5m3/Trip	20	Trips		

13	Cement-50kgs	20	Bags		
14	White cement - 50kg	120	Bags		
15	Gypsum powder (ANDIKA)	100	Bags		
16	400 x 250mm ceramic wall tiles (1.5 Sqm/Box)	30	Box		
	Expansion Joints				
17	20mm Thick; bituminous felt or any approved material	158	M2		
	SUB-TOTAL FOR FINISHING				
D.	PAINTING & DECORATION				
1	Emulsion Paint - 20 LTR	80	buckets		
2	Weather guard Paint - 20 LTRs	32	buckets		
3	Washable paint -20 LTRS (Light blue green)	140	buckets		
4	Primer paint -20 LTRs	30	buckets		
5	Solvent - 5LTRS	40	TIN		
6	Brush 3"	30	Pcs		
7	Roller	30	Pcs		
8	Scrap tool	30	Pcs		
9	Spatula	20	Pcs		
10	Gloss paint-4LTR	18	TIN		
11	olyurethane clear varnish on timber surfaces	16	Bucket		
12	Bitumen paint - 4Litres	20	TIN		
	SUB-TOTAL FOR PAINTING&DECORATION				
	GENERAL SUMMARY				AMOUNT
					TZS
	TARIME ADMINISTRATION BLOCK				
A.	CEILING				
B.	DOOR				
C.	FINISHING				
D.	PAINTING & DECORATION				
	TOTAL MATERIALS COST	TZS			-